

NO-A187 714


HYDRAULIC MODEL INVESTIGATION: WALNUT CREEK
FLOOD-CONTROL PROJECT CONTRA. (U) ARMY ENGINEER
WATERWAYS EXPERIMENT STATION VICKSBURG MS HYDRA.
W G DAVIS OCT 87 WES/TR/HL-87-14


1/1

UNCLASSIFIED

F/G 13/2

ML






MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A



US Army Corps
of Engineers

AD-A187 714



HYDRAULICS



LABORATORY

TECHNICAL REPORT HL-87-14

WALNUT CREEK FLOOD-CONTROL PROJECT CONTRA COSTA COUNTY, CALIFORNIA

Hydraulic Model Investigation

by

W. G. Davis

DTIC FILE COPY

Hydraulics Laboratory

DEPARTMENT OF THE ARMY
Waterways Experiment Station, Corps of Engineers
PO Box 631, Vicksburg, Mississippi 39180-0631



October 1987

Final Report

Approved For Public Release, Distribution Unlimited

DTIC
ELECTE
DEC 21 1987
S H D

Prepared for US Army Engineer District, Sacramento
Sacramento, California 95814-4794

87 12 16 262

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE

REPORT DOCUMENTATION PAGE				Form Approved OMB No 0704-0188	
1a REPORT SECURITY CLASSIFICATION Unclassified			1b ABSTRACT SECURITY CLASSIFICATION A187714		
2a SECURITY CLASSIFICATION AUTHORITY			3 DISTRIBUTION/AVAILABILITY OF REPORT Approved for public release; distribution unlimited.		
2b DECLASSIFICATION/DOWNGRADING SCHEDULE					
4 PERFORMING ORGANIZATION REPORT NUMBER(S) Technical Report HL-87-14			5 MONITORING ORGANIZATION REPORT NUMBER(S)		
6a NAME OF PERFORMING ORGANIZATION USAEWER Hydraulics Laboratory		6b OFFICE SYMBOL (If applicable) WENHNS-L		7a NAME OF MONITORING ORGANIZATION	
6c ADDRESS (City, State, and ZIP Code) PO Box 631 Vicksburg, MS 39180-0631		7b ADDRESS (City, State, and ZIP Code)			
8a NAME OF FUNDING/SPONSORING ORGANIZATION USAEW, Sacramento		8b OFFICE SYMBOL (If applicable)		9 PROCUREMENT INSTRUMENT IDENTIFICATION NUMBER	
8c ADDRESS (City, State, and ZIP Code) 670 Capitol Mall Sacramento, CA 95814-4794		10 SOURCE OF FUNDING NUMBERS			
		PROGRAM ELEMENT NO		PROJECT NO	TASK NO
					WORK UNIT ACCESSION NO
11 TITLE (Include Security Classification) Walnut Creek Flood-Control Project, Contra Costa County, California; Hydraulic Model Investigation					
12 PERSONAL AUTHOR(S) Davis, W. G.					
13a TYPE OF REPORT Final report		13b TIME COVERED FROM _____ TO _____		14 DATE OF REPORT (Year, Month, Day) October 1987	
15 PAGE COUNT 68					
16 SUPPLEMENTARY NOTATION Available from National Technical Information Service, 5285 Port Royal Road, Springfield, VA 22161.					
17 COSAT CODES			18 SUBJECT TERMS (Continue on reverse if necessary and identify by block number)		
FIELD	GROUP	SUB-GROUP	Channel improvement Walnut Creek		
			Hydraulic models		
			San Ramon Creek		
19 ABSTRACT (Continue on reverse if necessary and identify by block number)					
<p>Tests were conducted on a 1:25-scale model of the Walnut Creek channel to determine the adequacy of proposed channel improvements for the Walnut Creek channel, the San Ramon Bypass Channel, and their junction. The model reproduced approximately 1,084 ft of the San Ramon Bypass Channel, 730 ft of the Walnut Creek channel upstream from the junction, with topography reproduced upstream from the entrance to the revised channel, and 640 ft of the existing Walnut Creek channel downstream from the junction. The model was constructed so that the slopes of the channels could be adjusted to reproduce various energy gradients equivalent to those resulting from different prototype Manning's n roughness factors.</p> <p>The slopes of the model were initially adjusted to produce an energy gradient resulting from a Manning's n roughness factor of 0.012 in the prototype. Unsatisfactory flow conditions were observed in the Walnut Creek channel upstream from the junction due to entrance conditions into the high-velocity channel. A wall was installed which bridged the</p> <p style="text-align: right;">(Continued)</p>					
20 DISTRIBUTION/AVAILABILITY OF ABSTRACT <input checked="" type="checkbox"/> UNCLASSIFIED/UNLIMITED <input type="checkbox"/> SAME AS RPT <input type="checkbox"/> DTIC USERS			21 ABSTRACT SECURITY CLASSIFICATION Unclassified		
22a NAME OF RESPONSIBLE INDIVIDUAL			22b TELEPHONE (Include Area Code)		22c OFFICE SYMBOL

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE

19. ABSTRACT (Continued).

access ramp and provided satisfactory flow conditions in the portion of Walnut Creek upstream from the junction. Flow exceeded the wall heights at several points downstream from the San Ramon-Walnut Creek junction for both design flows with their maximum concurrent flows.

A 40-ft-long divider extension installed at the junction greatly improved flow conditions in the channel downstream and eliminated overtopping of the channel walls.

The slopes of the high-velocity channel were adjusted to reproduce the energy gradient resulting from a Manning's n roughness factor of 0.014 in the prototype. For both design flow conditions, overtopping of the wall heights was observed in the Walnut Creek channel. The width of the San Ramon Bypass Channel was reduced by 1 ft to 23 ft just upstream of the junction and the channel alignment was improved at the junction; the slope of the Walnut Creek channel was increased to 0.005 ft/ft downstream from the junction with this slope maintained in the San Ramon Bypass Channel upstream from the junction to sta 584+98; and the slope of the Walnut Creek channel upstream from the junction was increased to 0.0185 ft/ft extending to sta 584+50. These modifications provided satisfactory flow conditions for both design flows in the high-velocity channels. However, by steepening the slopes in the Walnut Creek channel, the upstream elevation of the channel invert was increased 1.5 ft, which increased the upstream pool elevation to an undesirable level. When flow through the access ramp was blocked, channel efficiency was increased and a satisfactory pool elevation was achieved with the design flow in Walnut Creek.

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE

DTIC
COPY
INSPECTED

COL Dwayne G. Lee, CE, is the Commander and Director of WES.
Dr. Robert W. Whalin is the Technical Director.

1

CONTENTS

	<u>Page</u>
PREFACE	1
CONVERSION FACTORS, NON-SI to SI (METRIC)	
UNITS OF MEASUREMENT	3
PART I: INTRODUCTION	5
The Prototype	5
Purpose and Scope of Model Investigation	5
PART II: THE MODEL	7
Description	7
Model Appurtenances	7
Scale Relations	7
PART III: TESTS AND RESULTS	10
Initial Tests ($n = 0.012$)	10
Increased Roughness ($n = 0.014$)	12
Recommended Design	14
PART IV: SUMMARY AND CONCLUSIONS	15
PHOTOS 1-22	
PLATES 1-25	

CONVERSION FACTORS, NON-SI TO SI (METRIC)
UNITS OF MEASUREMENT

Non-SI units of measurement used in this report can be converted to SI
(metric) units as follows:

<u>Multiply</u>	<u>by</u>	<u>To Obtain</u>
acres	4,046.873	square metres
cubic feet	0.02831685	cubic metres
degrees (angle)	0.01745329	radians
feet	0.3048	metres
miles (US statute)	1.609347	kilometres




Figure 1. Vicinity map

WALNUT CREEK FLOOD-CONTROL PROJECT
CONTRA COSTA COUNTY, CALIFORNIA
Hydraulic Model Investigation

PART I: INTRODUCTION

The Prototype

1. The Walnut Creek Flood-Control Project is located 15 miles* east of San Francisco Bay in a depression between the Berkeley Hills and Mount Diablo (Figure 1). Walnut Creek flows in or near the cities of Walnut Creek, Concord, Pleasant Hill, and Martinez, California, on its way to the Suisun Bay. All of the planned improvements are located in Contra Costa County, California. The project was authorized in 1960 as a channel improvement project with earth- and rock-lined trapezoidal channels approved for the lower reaches of Walnut Creek and open concrete rectangular channels approved for the upper reaches of Walnut Creek and the San Ramon Bypass Channel through the highly urbanized area of the city of Walnut Creek. The project will provide flood protection to about 6,670 acres in the floodplain at and below the city of Walnut Creek.

2. The model study was concerned primarily with the proposed San Ramon Bypass Channel and its junction with the Walnut Creek channel in the city of Walnut Creek.

Purpose and Scope of Model Investigation

3. The purpose of the model investigation was to determine the adequacy of and develop desirable modifications to the proposed San Ramon Bypass Channel, the Walnut Creek-San Ramon junction, and the entrance to the revised Walnut Creek channel with design flow conditions. A physical model study of the system was desired because of the possibility of significant cross waves generated in curves and at the junction and turbulence at the junction and transitions. Specifically, the model study was to determine

* A table of factors for converting non-SI units of measurement to SI (metric) units is presented on page 3.

- a. Flow conditions and water-surface profiles throughout the high-velocity channels for Manning's n roughness values of 0.012 and 0.014 during the following 100-year frequency flow conditions.

<u>Waterway</u>	<u>Design Flow Upstream of Junction, cfs</u>	<u>Concurrent Flow, cfs</u>	<u>Combined Flow, cfs</u>
Walnut Creek	10,000	11,500	21,500
San Ramon Bypass	15,200	6,800	22,000

- b. Flow conditions resulting from expansions, contractions, and confluence.
- c. Effective methods for modifying the channels to increase the hydraulic capacity and improve flow conditions.

PART II: THE MODEL

Description

4. The model, constructed to a scale of 1:25, reproduced approximately 1,084 ft of the San Ramon Bypass Channel, 730 ft of the Walnut Creek channel upstream from the junction, with topography reproduced upstream from the entrance to the revised channel, and 640 ft of the existing Walnut Creek channel downstream from the junction (Figure 2, Plates 1 and 2). The model was constructed of transparent plastic with the invert slopes adjustable to reproduce various energy gradients equivalent to those resulting from different prototype Manning's n roughness factors. Portions of the high-velocity channel requiring superelevation were constructed of concrete with a very smooth finish. The portion of Walnut Creek consisting of natural channel was molded in sand and cement mortar to sheet metal templates.


5. The coefficient of roughness of the model surface of the channels had previously been determined to be approximately 0.009 (Manning's n). Basing similitude on the Froudian relation, this n value would be equivalent to a prototype n of 0.0154. The n value used in the design and analysis of the prototype channels varied from 0.012 to 0.014; therefore supplementary slopes were added to the model to correct for this difference in the n values of the model and prototype.

Model Appurtenances


6. Water used in the operation of the model was supplied by a circulating system. Discharges were measured with venturi meters installed in the flow lines and were baffled when entering the model. Water-surface elevations were measured with point and rule gages. Different designs, along with various flow conditions, were recorded photographically.

Scale Relations

7. The accepted equations of hydraulic similitude, based on Froudian relations, were used to express mathematical relations between the dimensions and hydraulic quantities of the model and prototype. General relations for



a. General view



b. Closeup of Walnut Creek-San Ramon junction

Figure 2. The 1:25-scale model

transference of model data to prototype equivalents are as follows:

<u>Characteristic</u>	<u>Dimension*</u>	<u>Model:Prototype</u>
Length	$L_r = L$	1:25
Area	$A_r = L_r^2$	1:625
Velocity	$V_r = L_r^{1/2}$	1:5
Time	$T_r = L_r^{1/2}$	1:5
Discharge	$Q_r = L_r^{5/2}$	1:3,125
Roughness Coefficient	$N_r = L_r^{1/6}$	1:1.71

* Dimensions are in terms of length.

Model measurements of discharge and water-surface elevations can be transferred quantitatively to prototype equivalents by means of the preceding scale relations.

PART III: TESTS AND RESULTS

8. Tests were conducted to observe general flow conditions and determine the adequacy of the proposed channel improvements for the Walnut Creek channel and the proposed San Ramon Bypass Channel. The Manning's n roughness coefficient of the prototype channels could range from 0.012 to 0.014 depending on the quality of construction.

Initial Tests ($n = 0.012$)

9. The invert slopes of the channels initially tested were adjusted to reproduce an energy gradient resulting from a Manning's n roughness factor of 0.012 in the prototype. Representatives from Office, Chief of Engineers (OCE), US Army, US Army Engineer Division, South Pacific, and US Army Engineer District, Sacramento, inspected the model and observed test runs on 31 January 1984. It was agreed that certain modifications to the model were needed before basic data such as water-surface profiles and photographs of flow conditions were recorded. These modifications included raising the walls near the inlet to the high-velocity channel on Walnut Creek (Plate 3) and placing a low weir in this area. The original design defined herein includes these changes. Water-surface profiles recorded for the 100-year frequency flow Q_{100} conditions in both Walnut Creek and the San Ramon Bypass Channel with the respective maximum concurrent flows are shown in Plates 4 and 5. These flow conditions are shown in Photos 1-6. The black lines shown on the walls of the channels are the proposed wall heights.

10. Satisfactory flow conditions were observed in Walnut Creek upstream from the junction with San Ramon Bypass Channel with discharges less than 7,000 cfs. When the discharge was increased to 7,000 cfs and greater, flow began to enter the channel through the access ramp (Photo 4c). This created unsatisfactory flow conditions which included standing waves that extended downstream to the junction.

11. At the upstream end of the concrete channel in Walnut Creek, a wall was installed which bridged the access ramp (Photo 7a, Plate 6) in an effort to improve flow conditions with discharges greater than 7,000 cfs. With this modification, flow conditions were significantly improved in the portion of Walnut Creek upstream from the junction with discharges greater than 7,000 cfs.

Water-surface profiles recorded with the 100-year frequency discharge in Walnut Creek of 10,000 cfs and the maximum concurrent discharge in the San Ramon Bypass Channel are shown in Plate 7. Flow conditions with this modification are shown in Photos 7b and 8.

12. Flow did not exceed the wall heights in the San Ramon Bypass Channel for any discharge observed. However, standing waves developed downstream from sta 586+50 which extended several hundred feet downstream for all discharges observed. These waves were caused, in part, by the channel alignment, which involved a 75-ft straight reach of channel positioned between two curved sections from sta 586+62.58 to sta 582+49.55.

13. Flow exceeded the wall heights at several points downstream from the San Ramon-Walnut Creek junction for both design flows with their maximum concurrent flows (Plates 4 and 5). Various divider wall extensions were tested in an effort to reduce the standing waves that developed downstream of the junction. Initially, a 10-ft-long extension was added to the divider wall. This extension changed the profiles in Walnut Creek somewhat, but water-surface elevations on the right wall exceeded the wall heights by 2 to 3 ft in two places. The divider was then extended 30 ft. This extension constricted flow in the Walnut Creek channel with the design flow in San Ramon Creek and a concurrent flow of 6,800 cfs in Walnut Creek and caused a hydraulic jump to form upstream from the divider. However, the waves downstream from the divider were reduced, and the wall heights were occasionally exceeded by only 1 ft in a few places. The wall was extended 63.8 ft to sta 581+75.8 where the existing Walnut Creek channel is 40 ft wide. This extension further constricted flow in the Walnut Creek channel and caused the hydraulic jump to move upstream from the divider and overtop the walls. In an effort to reduce the constriction of flow in the Walnut Creek channel, various alignments of the 63.8-ft-long extension were tested. The best alignment was with the nose of the divider 21.25 ft from the left wall. However, the hydraulic jump still formed about 175 ft upstream from the divider, and there was slight overtopping of the walls. The wall extension length was reduced to 40 ft. Of the various alignments tested with this wall, the wall centered in the channel was found to be optimum. Although flow was restricted in the Walnut Creek channel and a hydraulic jump formed upstream from the divider with the design flow of 15,200 cfs in San Ramon Creek and the concurrent flow of 6,800 cfs in Walnut Creek, flow did not overtop the walls. With the design flow of 10,000 cfs in

Walnut Creek and the concurrent flow of 11,500 cfs in San Ramon Creek, there was an occasional splashover of flow at sta 581+20, but this was insignificant. Flow conditions were greatly improved in the channel downstream from the divider. The 40-ft-long divider extension was determined to be the optimum length with a Manning's n value of 0.012. Water-surface profiles with various divider extensions are shown in Plates 8-17. Flow conditions are shown in Photos 9-18.

Increased Roughness ($n = 0.014$)

14. The slopes of the model were adjusted to reproduce the energy gradient for a roughness value (Manning's n) of 0.014. These tests were conducted with the channel improvements installed that were recommended from previous tests conducted with the channel invert slopes adjusted to reproduce a Manning's n roughness factor of 0.012. These improvements included a wall that bridged the access ramp in Walnut Creek and a 40-ft-long divider extension at the San Ramon-Walnut Creek junction.

15. Water-surface profiles recorded for the 100-year frequency flow conditions in both Walnut Creek and San Ramon Bypass Channels with respective maximum concurrent flows are shown in Plates 18 and 19. Flow conditions are shown in Photos 19 and 20.

16. Flow did not exceed the wall heights in the San Ramon Bypass Channel for any of the discharges tested. With the design flow of 15,200 cfs in the San Ramon Bypass Channel and a concurrent flow of 6,800 cfs in Walnut Creek, a hydraulic jump formed in the Walnut Creek channel upstream from the junction which occasionally overtopped the existing wall heights. Flow occasionally exceeded the wall heights by 1 to 2 ft at sta 581+65, as shown in Plate 18 and Photo 19b.

17. With the design flow of 10,000 cfs in Walnut Creek and a concurrent flow of 11,500 cfs in the San Ramon Bypass Channel, flow exceeded the wall heights by only 1 ft in a few places, but overtopped the walls by as much as 5 ft from sta 577+85 to sta 579+10, as shown in Plate 19 and Photo 20a.

18. Additional channel improvements were needed to reduce the excessive overtopping of the channel walls. These channel improvements, designated the type 2 design channel, included decreasing the width of the San Ramon Bypass Channel from 24 to 23 ft from sta 587+70 to sta 582+24.37, improving the

channel alignment at the junction (Plate 20), adjusting the invert slope in the Walnut Creek channel to 0.005 ft/ft from sta 582+37.37 to sta 576+00 (this slope was maintained in the San Ramon Bypass Channel from the junction with Walnut Creek upstream to sta 584+98), and adjusting the invert slope in the Walnut Creek channel to 0.0185 ft/ft from sta 584+50 to sta 582+37.37.

19. Water-surface profiles measured with the type 2 design channel for the 100-year frequency flow conditions in both Walnut Creek and the San Ramon Bypass Channels with respective maximum concurrent flows are shown in Plates 21 and 22. These flow conditions are shown in Photo 21. Satisfactory flow conditions were observed in the San Ramon Bypass Channel for all discharges tested. With the design flow of 15,200 cfs in the San Ramon Bypass Channel and a concurrent flow of 6,800 cfs in Walnut Creek, a hydraulic jump formed in the Walnut Creek channel upstream from the junction which occasionally overtopped the wall by 1 to 2 ft between sta 583+20 and 581+50, as shown in Plate 21 and Photo 21b. With the design flow of 10,000 cfs in Walnut Creek and a concurrent flow of 11,500 cfs in the San Ramon Bypass Channel, flow exceeded the wall heights by 1.5 ft maximum at sta 581+20, as shown in Plate 22 and Photo 21a.

20. The previous modification, which involved steeper slopes in Walnut Creek, resulted in the invert of the entrance to the concrete channel being increased from el 104* to el 105.5. This increase in elevation caused an increase in the upstream pool elevation. Tests were conducted to determine modifications, which did not include widening the channel, that would reduce the upstream pool elevation without affecting flow conditions at and downstream of the junction.

21. In an effort to improve the entrance conditions in the Walnut Creek channel, the access ramp was completely blocked off and the upstream face of the channel invert was sloped downward. This design resulted in a reduction in the upstream pool elevation from el 133.5 to el 132.7 for the 100-year frequency flow, as shown in Plate 23. The left side was then modified to simulate a symmetrical entrance approach to the channel (Plate 24, Photo 22a). Test results indicated the upstream pool elevation was lowered to el 132.6 for the 100-year frequency flow with this modification. Water-surface profiles

* All elevations (el) and stages cited herein are in feet referred to the National Geodetic Vertical Datum.

and photographs of flow conditions in the approach channel are shown in Plate 25 and Photo 22, respectively. Since the streamlined left wall entrance decreased the water surface only by 0.1 ft, and would involve major structural modifications, it would not be feasible to incorporate this modification into the design.

Recommended Design

22. The overall recommended design determined from test results for a Manning's n of 0.012 incorporates into the original proposed design raising the walls near the inlet to the high-velocity channel on Walnut Creek (Plate 3), bridging the access ramp (Plate 6), and lengthening the divider extension to 40 ft.

23. The overall recommended design determined from test results for a Manning's n of 0.014 incorporates into the original proposed design raising the walls near the inlet to the high-velocity channel on Walnut Creek (Plate 3), bridging and blocking off the access ramp (Plate 6), increasing the invert slope in the Walnut Creek channel to 0.0185 ft/ft from sta 584+50 to sta 582+37.37, decreasing the width of the San Ramon Bypass Channel from 24 to 23 ft (Plate 20), improving the channel alignment at the junction, increasing the slope in the Walnut Creek channel to 0.005 ft/ft downstream from the junction to sta 576+00, and lengthening the divider extension to 40 ft.

PART IV: SUMMARY AND CONCLUSIONS

24. Tests to determine the adequacy of channel improvements for Walnut Creek indicated that the original design with certain modifications would effectively contain design flow conditions in the Walnut Creek channel improvement project.

25. It was anticipated that the Manning's n roughness coefficient of the prototype concrete-lined channel could range from 0.012 to 0.014, depending on the quality of construction. Water-surface elevations would be slightly higher with the larger n value, and flow velocities and waves created by disturbances would be slightly higher with the smaller n value. Thus, tests were conducted to simulate the energy gradient resulting from both of the n values.

26. With a Manning's n value of 0.012 reproduced, entrance conditions into the high-velocity channel on Walnut Creek caused standing waves to develop that extended downstream to the junction due to unsymmetrical approach and inflow into the channel through the access ramp. By blocking off the access ramp, flow conditions and channel efficiency were significantly improved.

27. Flow did not exceed the wall heights in the San Ramon Bypass Channel for the design discharges. However, standing waves developed downstream from sta 586+50 that may have been caused by the channel alignment, which involved a 75-ft straight reach of channel positioned between two curved sections. Flow exceeded the wall heights at several points downstream from the junction for both design flows. A 40-ft-long divider extension greatly improved flow conditions and alleviated overtopping of the walls.

28. The slopes of the Walnut Creek and San Ramon Bypass Channels were adjusted to reproduce the energy gradient for a roughness value of 0.014. This increase in roughness caused overtopping of the wall heights in the Walnut Creek channel for both design discharges. A new section of channel was installed on the San Ramon Bypass which reduced the channel width from 24 to 23 ft and improved the channel alignment at the junction. The invert slope in the Walnut Creek channel was increased to 0.005 ft/ft downstream from the junction and was increased to 0.0185 ft/ft upstream from the junction. With these modifications installed, both design flow conditions were adequately contained in the channels.



a. Dry bed




b. Discharge 11,500 cfs





c. Discharge 11,500 cfs


Figure 1. Discharge of water from the canal. The discharge is 11,500 cfs. The water is flowing over the concrete structure.



a. Dry bed




b. Discharge 11,500 cfs



c. Discharge 15,000 cfs


Photo 1. San Ramon Bypass Channel, looking in the right side of the channel between station 1+000 and 1+050, on 11/1/71.



a. Dry bed




b. Discharge 11,500 cfs in San Ramon
Discharge 10,000 cfs in Walnut Creek



c. Discharge 15,000 cfs in San Ramon
Discharge 8,000 cfs in Walnut Creek

Figure 1. San Ramon-Lake Channel-Walnut Creek Junction, looking
downstream from the south side of the channel, a. 0.00




a. Dry bed




b. In channel, bed

Photo 4. Walnut Creek, looking downstream at the entrance to the velocity channel, on 11/11/67.




c. Discharge 10,000 cfs

Photo 4. (Concluded)




a. Discharge 6,800 cfs in Walnut Creek
Discharge 15,200 cfs in San Ramon




b. Discharge 1,100 cfs in Walnut Creek
Discharge 11,000 cfs in San Ramon

NOTE: Walnut Creek is a tributary of the San Ramon River. The bridge is located on the left bank of the river, just upstream of the confluence.




a. Discharge 21,500 cfs




b. Discharge 22,500 cfs

FIGURE 1. Walnut Creek Dam and Walnut Creek Diversion Dam. (a) Discharge 21,500 cfs; (b) Discharge 22,500 cfs.



a. Dry bed



b. Log jammed bridge

Photo 7. Walnut Creek, looking downstream at the entrance to the high-velocity channel with the log jammed bridge.






Figure 1. Walnut Creek-San Ramon Bypass Channel junction, looking upstream in the left abutment of the bridge. Channel, 400 ft long; pump bridge, $n = 0.012$. Discharge 10,000 cfs in Walnut Creek.




a. Discharge 21,500 cfs




b. Discharge 22,000 cfs

Photo 9. Walnut Creek-San Ramon bypass channel junction, looking in the left side of the channel with the 10-ft divider extension installed, a. and b.





a. Discharge 21,500 cfs





b. Discharge 22,000 cfs

Fig. 10. Walnut Creek, looking downstream in the left side of the channel
 at 2000 ft, 1720+00 and 1773+00 with the 10-ft divider extension installed,
 $n = 0.017$




a. Discharge 21,500 cfs




b. Discharge 11,000 cfs

Photo 11. Walnut Creek-Ga. Dam, Project No. 1. (a) View of the right side of the channel with the right divider wall extension, at discharge of 21,500 cfs. (b) View of the right side of the channel with the right divider wall extension, at discharge of 11,000 cfs.




a. Discharge 21,500 cfs




b. Discharge 22,000 cfs

Photo 12. Walnut Creek, looking downstream in the left side of the channel between sta 582+50 and 578+00 with the 30-ft divider extension installed.
 $n = 0.012$




a. Discharge 21,500 cfs




b. Discharge 15,000 cfs

The model was tested at two different discharge rates, 21,500 cfs and 15,000 cfs. The water level was measured at various points along the structure, and the flow was observed through the structure. The results of the tests are shown in the following table.




4. Diagram 1, 1/2, 1/4




5. Diagram 1, 1/2, 1/4

The following table shows the results of the tests conducted on the model. The data is presented in a tabular format, with columns for various parameters and rows for different test conditions. The table is partially obscured by the high-contrast image, but the structure of the data is clear.




a. Discharge 21,500 cfs




b. Discharge 22,000 cfs


Photo 16. Walnut Creek, looking downstream in the left abutment between sta 582+50 and 578+00 with the 63.8-ft divider extension installed and its nose at 21.25 ft from the left wall, etc.




a. Discharge 21,500 cfs



The model was constructed of aluminum and was used to study the flow of water over a series of rectangular blocks. The blocks were arranged in a row and the water was flowing from left to right. The model was used to study the flow of water over a series of rectangular blocks.




a. Discharge 21,500 cfs




b. Discharge 22,000 cfs

Photo 13. Walnut Creek, looking downstream in the left side of the channel between sta 582+50 and 578+00 with the 40-ft divider extension installed, $n = 0.012$




a. Discharge 21,500 cfs




b. Discharge 21,000 cfs

Photo 17. Walnut Creek-San Ramon Express Tunnel junction, looking
in the left side of the channel with the 40-ft divider extension
installed, $q = 0.214$




a. Discharge 21,500 cfs




b. Discharge 12,000 cfs

Photo 70. Walnut Creek, looking downstream in the left side of the channel between 01+100 and 01+170+00 with the 40-ft divider extension installed, 11/1/74.




3. Discharge of water



4. Discharge of water



a. Dry bed




b. Discharge 10,000 cfs


Photo 22. Walnut Creek, looking downstream at the entrance to the high-velocity channel with the symmetrical entrance (Continued)




c. Discharge 10,000 cfs, confetti accents surface flow patterns; exposure time 10 sec (prototype)

Photo 22. (Concluded)






PLAN





ELEVATION



**DETAILS OF RAISED WALL HEIGHT
ORIGINAL DESIGN**


NOTE: ENTIRE LEFT WALL OF ACCESS RAMP
RAISED TO EL 134.0




LEGEND
 --- TOP OF LEFT WALL
 --- TOP OF RIGHT WALL
 --- LEFT INVERT
 --- RIGHT INVERT

WATER-SURFACE PROFILES

WALNUT CREEK 6.800 cfs
 SAN RAMON CREEK (Q_{10}) 15.200 cfs
 ORIGINAL DESIGN
 $n = 0.012$




WITH LEFT WALL OF ACCESS HAMPSHIRE THROUGH VALLEY IN




LEGEND
 — LEFT SIDE OF CHANNEL
 --- CENTER OF CHANNEL
 --- RIGHT SIDE OF CHANNEL

WATER-SURFACE PROFILES

WALNUT CREEK (Q_{100}) 10,000 cfs
 SAN RAMON CREEK 11,500 cfs
 ORIGINAL DESIGN
 n 0.012





PLAN



ELEVATION
LEFT WALL

DETAILS OF RAISED WALL HEIGHT
ACCESS RAMP BRIDGED



LEGEND

— LEFT SIDE OF CHANNEL

- - - CENTER OF CHANNEL

--- RIGHT SIDE OF CHANNEL


WATER-SURFACE PROFILES

WALNUT CREEK (Q_{100}) 10,000 cfs


SAN RAMON CREEK 11,500 cfs

ACCESS RAMP BRIDGED

$n : 0.012$



10-FT DIVIDER EXTENSION
CENTERED IN CHANNEL



LEGEND

—○— LEFT SIDE OF CHANNEL

—○— CENTER OF CHANNEL

—○— RIGHT SIDE OF CHANNEL

WATER-SURFACE PROFILES


WALNUT CREEK 6,800 cfs

SAN RAMON CREEK (Q_{100}) 15,200 cfs


10.0-FT DIVIDER EXTENSION

ACCESS RAMP BRIDGED


$n = 0.012$



WALNUT CREEK (Q₁₀₀)
SAN RAMON CREEK
100-FT DIVIDER EXTENSION
ACCESS RAMP BRIDGED
n = 0.012



30-FT DIVIDER EXTENSION
CENTERED IN CHANNEL





LEGEND


- LEFT SIDE OF CHANNEL
- - - CENTER OF CHANNEL
- - - RIGHT SIDE OF CHANNEL

WATER-SURFACE PROFILES


WALNUT CREEK 6,800 cfs
 SAN RAMON CREEK (Q_{100}) 15,200 cfs
 30.0-FT DIVIDER EXTENSION
 ACCESS RAMP BRIDGED
 $n = 0.012$








INVERT ELEVATION IN
CENTERS OF CHANNEL





WATER-SURFACE PROFILES

WALNUT CREEK (Q=) 10,000 cfs
 SAN RAMON CREEK 11,500 cfs
 63.8-FT DIVIDER EXTENSION
 ACCESS RAMP BRIDGED
 n 0.012



RIGHT DIVIDER EXTENSION





LEGEND


- LEFT SIDE OF CHANNEL
- CENTER OF CHANNEL
- RIGHT SIDE OF CHANNEL


WATER-SURFACE PROFILES


WALNUT CREEK	6,800 cfs
SAN RAMON CREEK (Q ₁₀)	15,200 cfs
63.8-FT DIVIDER EXTENSION	
NOSE AT 21.25 FT	
ACCESS RAMP BRIDGED	
n = 0.012	













PI A - Q CURVE DATA
(Δ 43.6°)

CIRCULAR CURVE		SPIRAL CURVES	
	UPSTREAM	DOWNSTREAM	
Δ_c	14.6828		
R	285	Δ_s 20.1244°	Δ_s 8.7928°
L	73.03	T_s 209.02	T_s 164.99
SE	3.82	L_s 200	L_s 87.5




PLAN

CHANNEL WIDTH AND
ALIGNMENT MODIFICATION



40-FT DIVIDER EXTENSION



LEGEND

— LEFT SIDE OF CHANNEL

- - - CENTER OF CHANNEL

... RIGHT SIDE OF CHANNEL

WATER-SURFACE PROFILES

WALNUT CREEK 6,800 cfs


SAN RAMON CREEK (Q_{100}) 15,200 cfs

40-FT DIVIDER EXTENSION

TYPE 2 DESIGN CHANNEL

ACCESS RAMP BRIDGED

$n = 0.014$



WATER-SURFACE PROFILES

WALNUT CREEK (Q_{100}) 10,000 cfs

SAN RAMON CREEK 11,500 cfs

40-FT DIVIDER EXTENSION

TYPE 2 DESIGN CHANNEL

ACCESS RAMP BRIDGED


$n = 0.014$

LEGEND


○ LEFT SIDE OF CHANNEL

— CENTER OF CHANNEL

● RIGHT SIDE OF CHANNEL



SYMMETRICAL
ENTRANCE



WALNUT CREEK (Q ₁₀₀)	10,000 cfs
SAN RAMON CREEK	11,500 cfs

SYMMETRICAL ENTRANCE
 $\eta = 0.014$

END
FILMED
FEB. 1988
DTIC